




CEPC Accelerator EDR Status and Perspectives

Jie Gao


IHEP






Contents

- Introduction
- CEPC Accelerator Design and Key Hardware R&D in TDR as Start of EDR
- CEPC EDR Goals, Scope, Plan, Progress status
- CEPC Site Implementation in EDR and Construction Plans
- CEPC technology Industrial preparations and international collaboration in EDR
- Summary






Worldwide High Energy Physics Goal Timelines and Common Efforts







CEPC Higgs Factory and SppC Layout in TDR/EDR

CEPC as a Higgs Factory: H, W, Z, upgradable to ttbar, followed by a SppC (a Hadron collider) ~125TeV 30MW SR power per beam (upgradable to 50MW), high energy gamma ray 100Kev~100MeV






TUNNEL CROSS SECTION OF THE ARC AREA



CEPC/SppC in the same tunnel






CEPC Accelerator System Parameters in TDR/EDR

Linac Booster Collider

Parameter	Symbol	Unit	Baseline
Energy	E_e / E_{e+}	GeV	30
Repetition rate	f_{rep}	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		пC	1.5 (3)
Energy spread	σ_E		1.5×10 ⁻³
Emittance	ε_r	nm	6.5

		tt	H	Ī	W		\overline{Z}
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis	sinjection
Circumfer.	km		100				
Injection energy	GeV				30		
Extraction energy	GeV	180	12	0	80	4	5.5
Bunch number		35	268	261+7	1297	3978	5967
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81
Beam current	mA	0.11	0.94	0.98	2.85	9.5	14.4
SR power	MW	0.93	0.94	1.66	0.94	0.323	0.49
Emittance	nm	2.83	1.2	26	0.56	0	.19
RF frequency	GHz	1.3					
RF voltage	GV	9.7	9.7 2.17 0.87 0.		.46		
Full injection from empty	h	0.1	0.14	0.16	0.27	1.8	0.8

	Higgs	Z	W	$tar{t}$
Number of IPs		2	2	
Circumference (km)		10	0.0	
SR power per beam (MW)		3	0	
Energy (GeV)	120	45.5	80	180
Bunch number	268	11934	1297	35
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Beam size at IP σ_x/σ_y (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7	2.5/4.9	2.2/2.9
Beam-beam parameters ξ_x/ξ_y	0.015/0.11	0.004/0.127	0.012/0.113	0.071/0.1
RF frequency (MHz)	650			
Luminosity per IP (10 ³⁴ cm ⁻² s ⁻¹)	5.0	115	16	0.5



Running scenarios: Higgs 10 years, Z 3 years, W 1 year, ttbar 5 years


CEPC Technical Design Report (TDR) includes:

- 1) CEPC Accelerator TDR
- 2) CEPC Detector TDRrd (rd=reference design) will be completed by June 2025




Perspectives -J. Gao

CEPC Collider Ring Daynamic Apertures





Studies of Beam-Beam Effects in CEPC



Beam-beam simulation results are consistent with the TDR parameter tables.

- Luminosity & Lifetime is evaluated by strong-strong simulation
- X-Z instability is well suppressed even considering Potential Well Distortion
- Lifetime optimization with both beam-beam\lattice nonlinearity is done




CEPC Key Technology R&D Status in TDR

Specification Met



Prototype Manufactured **X**





Key technology R&D in TDR spans all component lists in CEPC	CDR


ST. INC.	
Accelerator	Fraction
Magnets	27.3%
Vacuum	18.3%
RF power source	9.1%
Mechanics	7.6%
✓ Magnet power supplies	7.0%
✓ SC RF	7.1%
Cryogenics	6.5%
Linac and sources	5.5%
✓ Instrumentation	5.3%
Control	2.4%
Survey and alignment	2.4%
Radiation protection	1.0%
SC magnets	0.4%
✓ Damping ring	0.2%



CEPC Accelerator International TDR Review and Cost Review June 12-16, and Sept. 11-15, 2023, in HKUST-IAS, Hong Kong



CEPC Accelerator TDR Review June 12-16, 2023, Hong Kong



Domestic Civil Engineering Cost Review, June 26, 2023, IHEP




CEPC Accelerator TDR Cost Review Sept. 11-15, 2023, Hong Kong



9th CEPC IAC 2023 Meeting Oct. 30-31, 2023, IHEP



Total



Distribution of CEPC Project total TDR cost of 36.4B RMB (~5.2USD)

Table 12,1.2: CEPC project cost breakdown, (Unit: 100,000,000 yuan)

100%

CEPC accelerator TDR has been completed and formally released on December 25, 2023:

http://english.ihep.cas.cn/nw/han/y23/202312/t20231229_654555.html

CEPC accelerator TDR has been published formally in Journal Radiation Detection Technology and Methods (RDTM) on June 3, 2024:

DOI: 10.1007/s41605-024-00463-y

https://doi.org/10.1007/s41605-024-00463-y



CEPC Milestones, Timeline and Human Resources

2012 2013 2015 2017 2018 2023 2027 2030 2035 Year 2025 **Human resources (TFE)** ~50 ~100 ~200 ~300 ~500 ~2800 ~2500

Year	Accelerator human resource	Accumulated accelerator spending Billion RMB	1	Proposal (2025) for CEPC entering 15th five year plan
2015	50	-	Investment perye	
2018	100	-	westi	
2023	200	0.2	= /	
2025	300	0.3		Year 36.4B RMB
2027	500	0.4		Total construction
2031	2800	9	139CA	CEPC Curceptual Design Report Vasce Seasons Technical Design Report
2035 CEPC	2500 kickoff meeting in	20 Sept. 2013	CEPICAPIC Onlinear Project Paper Onlinear Project Paper Onlinear Project Paper Onlinear Pa	

2012.9 2013.9 2015.3 2017.4 2018.11

2023.12 2024

2027

~2035

CEPC proposed

Pre-CDR Progress report CDR

TDR

EDR start of construction

Completion



CEPC Engineering Design Report (EDR) Goal

2012.9 CEPC proposed

2015.3 Pre-CDR

2018.11 CDR

2023.10 TDR

CEPC Proposal
CEPC Detector
reference design

2025

2027 15th five year plan

EDR Start of construction

CEPC EDR Phase General Goal: 2024-2027

After completion CEPC accelerator TDR in 2023, CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC proposal to be presented to and selected by Chinese government around 2025 for the construction start during the "15th five year plan (2026-2030)" (for example, around 2027) and completion around 2035 (the end of the 16th five year plan).

CEPC EDR includes accelerator and detector (TDRrd)

CEPC detector TDR reference design (rd) will be released by June 30, 2025


CEPC Accelerator EDR Phase goals, scope and the working plan (preliminary) of 35 WGs summarized in a documents of 33 pages to be reviewed by IARC in Spet. 18-20, 2024





CEPC Magnet Automatic Production Line in EDR

Mei Yang/Wen Kang_




Plan: Middle of 2024 design completed, To be completed in 2025





Yongsheng Ma



Production line of NEG coating, spraying

AGV(Automatic Guided Vehicle) transport

7-axis robot for assembling

Plan: Middle of 2024 design completed. Technical design review will be done soon. To be completed in 2025




CEPC Accelerator SRF Development in EDR


Jiyuan Zhai/Peng Sha








CEPC collider ring 650MHz 2*cell short test module has been completed in TDR phase






The collider Higgs mode for 30 MW SR power per beam will use 32 units of 11 m-long collider cryomodules will contain six 650 MHz 2-cell cavities, and therefore, a full size 650 MHz cryomodule will be developed in EDR



CEPC Accelerator Main EDR Development: Klystrons

Zusheng Zhou




Parameters	Value
Frequency	5720 MHz
Output Power	80MW
Pulsed width	2.5us
Repetition rate	100Hz
Gain	54 dB
Efficiency	47%
3dB bandwith	±5MHz
Beam voltage	420 kV
Beam current	403 A
Focusing field	0.28 T


C band 5720MHz 80MW Klystron

C band 5720MHz 80MW Klystron design completed

Technical assessment has been done on August 12, 2024, start construction Soon, to be completed on 2025





CEPC Accelerator EDR Status and Perspectives -J. Gao




Joint workshop between UK and IHEP, Oct. 14-15, 2024, Korea














Correctors: mechanical design completed

Dual aperture quadrupole: block iron core and new cooling and power line design in EDR










Sextupole magnets under design




CEPC MDI in EDR






CEPC MDI Development in EDR

Haijing Wang, Yinshun Zhu_ Rui Ge/Mei Li








CEPC SC Quadrupole Magnet Design with CCT Coil

Design parameters of Q1a, Q1b, Q2 magnet with CCT coil @ Higgs mode

Magnet name	Qla	Q1b	Q2
Field gradient (T/m)	142.3	85.4	96.7
Magnetic length (mm)	1.21	1.21	1.5
Excitation current (A)	780	650	770
Conductor (HTS or LTS)		0.8 or 0.7mm in d	iameter
Maximum dipole field in aperture (Gs)	226	124	127
Stored energy (KJ)	16.7	15.2	22.9
Peak field in coil (T)	4.3	3.4	4.5
Integrated field harmonics		<2×10 ⁻⁴	
(Single aperture) Coil inner radius (mm)	20	26	31
(Single aperture) Coil outer diameter (mm)	30.5	39	44
Magnet mechanical length (m)	1.22	1.23	1.53
Net weight (kg)	25	32	43
Total weight of Q1a, Q1b, Q2 (kg)		100	
(For comparison, old net weight with iron option (kg))		Q1a: 93, Q1b:124, fotal weight of Q1a, Q	








CEPC Alignment and Installation Plan in EDR

Alignment accuracy requirement

Component	Δx (mm)	Δy (mm)	$\Delta\theta_{z}$ (mrad)
Dipole	0.10	0.10	0.10
Arc Quadrupole	0.10	0.10	0.10
IR Quadrupole	0.10	0.10	0.10
Sextupole	0.10*	0.10*	0.10



Component Pre-alignment






GPS receiver Embedded board Bedrock pile cast point Permanent point CEPC Accelerator EDR Status and

*implement beam-based alignment

Perspectives -J. Gao

Surface Control network (14Points)





Tunnel Control network


Backbone Control network (short-line: 300 m) clong like: 600 m) Oct. 14-15, 2(interval of 6 meters)






CEPC Installation Strategy Study in EDR

CEPC component list and quantities



Linac: 1.6km
TL:1.5km
Circumference of ring tunnel:100km
Collider: 100km
Booster: 100km
Tunnel cross section: 6X5m




Component	Collider Ring	Booster	Linac, DR, TL	Total
Dipole	16258	14866	135	31259
Quadrupole	4148	3458	714	8320
Sextupole	3176	100	72	3348
Corrector	7088	2436	275	9799
BPM 、 PR 、 DCCT 、 kicker	3544	2408	180	6132
Septum Magnet	68	32	2	102
Kicker	8	8	2	18
Cryomodule	32	12		44
Electrostatic separator	32			32
Collimator dump	36		8	44
Superconducting Magnets	4			4
Solenoid			37	37
Accelerating structure			577	577
Cavity			4	4
Electron Source			1	1
Positron Source			1	1
Detector	2			2
Total	34396	23320	2008	59724

SPPC



CEPC Tunnel Mockup for Installation in EDR

Haijing Wang



A 60 m long tunnel mockup, including parts of arc section and part of RF section

To demonstrate the inside tunnel alignment and installation, especially for booster installation on the roof of the tunnel


Technical review has been done on August 16, 2024, and construction will start soon



Advanced Technologies Development in Progress

9

CEPC Plasma Injector (alternative option) and TF Plan




PWFA/LWFA TF based on BEPC-II Linac and HPL has been founded by CAS 90M RMB in Sept. 2023

Under development in the experimental hall #10 of BEPC-II




IBS Technology for High Field Magnets



J_e of IBS expected to be similar as ReBCO in 2020s with better mechanical properties and lower costready for mass applications in ultra high field magnets

9

CEPC Polarized Beam Studies(alternative option)



Key issues of study:

- Energy calibration in collider ring with transverse polarization (self polarization & inj. polarization)
- Longitudinal polarization for collision
- · Polarization beam injection, positron polarization and ramping in booster


CEPC Accelerator EDICSorps, Plan and Status of Cites

The CEPC LARC Meeting in 2024, Sept. 18-28, 2024, IHEP

Key technology development for polarized electron beam generation, measurement and manipulation have been started

9

SppC HF Magnet Development



Picture of LPF1-U


Dual aperture superconducting dipoles achieve 12T@4.2 K and 14T@4.2K entirely fabricated in China. The next step is reaching 16-20T

CSPC Accelerator (CSR Scripe, Plot prof. States -), Cito.



CEPC EDR Selection and Civil Engineering Design Progresses


Preliminary EDR site selection report (completed)
And detailed site geological study will start soon in 2024



The number of shafts is under optimization

Plan-4 (bleu colored)














Arc region shaft cross section design

SRF region shaft cross section design

On site geological investigation




CEPC Conventional Facility and Civil Engineering in EDR






CEPC Site Implementation and Construction Plans

CEPC site implementation plan in EDR



The EDR site selection and the site dependent civil engineering design works has been started.

CEPC construction plan





Participating and Potential Collaborating Companies in China (CIPC) and Worldwide

System Magnet Power supplier 3 Vacuum Mechanics **RF** Power 6 SRF/RF Cryogenics Instrumentation Control Survey and 10 alignment Radiation 11 protection

e-e+Sources

CEPC Industrial Promotion Consortium (CIPC, established in Nov. 2017)



Potential international collaborating suppliers worldwide







CEPC Industrial Preparation



Large-scale Cryogenic Refrigeration & Liquefaction Equipment S 中国電池




(CIPC member)

CEPC 650MHz 800kW CW High Efficiency Klystrons


First 18kW@4.5K helium refrigerator fabricated in in China passes inspection

- -It was developed by the Institute of TIPC, CAS, and integrated and manufactured by Fullcryo.
- -The super large horizontal cold box with a length of 28m and a diameter of 4.2m achieves ultra-high vacuum and extremely low leakage.
- -The horizontal cold box at megawatt-level is the largest of its kind in China and even in the world.
- -The horizontal cold box system has exceeded the set targets.
- On-site testing: 1. The airtightness test of each internal channel revealed a pressure drop of 0, surpassing the target value of 0.02 bar. 2. The overall leakage rate is 9.1×10-10 Pa.m3/s, surpassing the target value of 1×10-7 Pa.m3/s.
- -Expected Goals: Achieving 3 operational mode adjustments: the cooling capacity ≥ 18kW@4.5K; the cooling capacity in the superfluid helium temperature range ≥4kW(a/2K).





北京中科富海低温科技有限公司 Beijing Sinoscience Fullcryo Technology CO., Ltd. (CIPC member)




Kumhan National Research Institute has successively developed 650MHz/800KW klystron sample tubes, 650MHz/800KW high-efficiency klystron sample tubes, 648MHz pulse klystron tubes, 650MHz/800KW multi-injection klystron beam tubes, and the latest 324MHz pulse ldystron tubes Electro vacuum products for 50 years. Provide high power thyristor of GL1536A in batches for BEPCII in 2012.

HE-RACING Technology and OTIC on SRF Technologies (CIPC members)











High RRR Nb sheet



1.3GHz cryomodule assembly

High RRR Nb ingod High RRR large grain Nb



(CIPC member)

2012 Michigan State University - FRIB 888250 Nb. 8.3 tors, 70% of the project 2014 Fermilab - LCLS I

BRR300 Nb: 5 tons, 50% of the project 2017 INFN and STFC - ESS

RRR300 Nb: 12.5 tons, 100% of the project


2019 185 - RISP, CERN - HL-LHC, Fermilab - PIP-II, Shanghai - SHINE 888300 nioblum material procurement in progress

CEPC booster and colliders: 2GeV 1.3GHz and 650MHz SRF accelerators (Higgs); 10GeV L3GHz and 650MHz SRF accelerators (ttar)

RF Shielding all Metal Gate Vacuum Valve

- Two prototypes of RF shielding All metal gate valve have been developed, and the leakage of one of them have been tested.
- The delivery inspection leakage test results for two valves , conducted by the manufacturer, were found to be < 1×109 mbar -L/s (30 times open and closed).
- The difference of leakage by IHEP & manufacture will be checked and retested in next.





 Tested by IHEP Expectation leakage < 1×10-3 mbar -L/s







CEPC in Synergy with other Accelerator Projects in China 29

Project name	Machine type	Location	Cost (B RMB)	Completion time
CEPC	Higgs factory Upto ttar energy	Led by IHEP, China	36.4 (where accelerator 19)	Around 2035 (starting time around 2027)
BEPCII-U	e+e-collider 2.8GeV/beam	IHEP (Beijing)	0.15	2025
HEPS	4 th generation light source of 6GeV	IHEP (Huanrou)	5	2025
SAPS	4th generation light source of 3.5GeV	IHEP (Dongguan)	3	2031 (in R&D, to be approved)
HALF	4th generation light source of 2.2GeV	USTC (Hefei)	2.8	2028
SHINE	Hard XFEL of 8GeV	Shanghai-Tech Univ., SARI and SIOM of CAS (Shanghai)	10	2027
S3XFEL	S3XFEL of 2.5GeV	Shenzhen IASF	11.4	2031
DALS	FEL of 1GeV	Dalian DICP	-	(in R&D, to be approved,)
HIAF	High Intensity heavy ion Accelerator Facility	IMP, Huizhou	2.8	2025
CIADS	Nuclear waste transmutation	IMP, Huizhou	4	2027
CSNS-II	Spallation Neutron source proton injector of 300MeV	IHEP, Dongguan	2.9	2029

The total cost of the accelerator projects under construction:39B RMB more than CEPC cost of 36.4B RMB




CEPC International Collaboration-1

CEPC attracts significant International participation and collaborations

Accelerator TDR report: 1114 authors from 278 institutes (including 159 International Institutes, 38 countries) Published in Radiation Detection Technology and Methods (RDTM) on June 3, 2024:

DOI: 10.1007/s41605-024-00463-y https://doi.org/10.1007/s41605-024-00463-y



- More than 20 MoUs have been signed with international institutions and universities
- CEPC International Workshop since 2014
- EU-US versions of CEPC WS since 2018
- Annual working month at HKUST-IAS (mini workshops and HEP conference) since 2015






CEPC International Collaboration-2

HKIAS23 HEP Conference, Feb. 14-16, 2023

https://indico.cern.ch/event/1215937/



The 2024 HKUST IAS Mini workshop and conference were held from Jan. 18-19, and Jan. 22-25, 2024, respectively.

https://indico.cern.ch/event/1335278/timetable/?view=standard

The 2025 HKUST IAS HEP conference: Jan. 13-17, 2025.

CEPC Workshop EU Edition (Barcelona, Spain), May 5-8, 2024

The 2023 International Workshop on Circular Electron Positron Collider, EUEdition, University of Edinburgh, July 3-6, 2023

https://indico.ph.ed.ac.uk/event/259/overview





The 2024 international workshop on the high energy Circular Electron Positron Collider (CEPC) will be held from Oct. 23-27, 2024, Hangzhou, China https://indico.ihep.ac.cn/event/22089/ The 2023 international workshop on the high energy Circular Electron Positron Collider (CEPC)

https://indico.ihep.ac.cn/event/19316/



Professor Peter Higgs passed away on **April 8, 2024**. We miss him.

The 2024 international workshop of CEPC, EU-Edition were held in Marseille, France, April 8-11, 2024. https://indico.in2p3.fr/event/20053/overview



FCPPNL, Bordeaux, France, June 10-14, 2024 https://indico.in2p3.fr/event/20434/overview



CEPC Accelerator IARC Review in EDR Phase (2024)

(Sept. 18-20, 2024, at IHEP)







CEPC International Accelerator Review Committee (IARC) Meeting was held from Sept. 18-20, 2024 at IHEP


The CEPC International Accelerator Review Committee (IARC) members visited IHEP 4th Generation 6GeV HEPS light source in Huairou campus of IHEP on Sept. 20, 2024 at IHEP

The CEPC International Accelerator Review Committee (IARC) members in the control room Of HEPS, and 30mA stored beam current have been reached during storage ring commissioning in Sept. 2024



CEPC Planning, Schedule and Teams

TDR (2023), EDR(2027), start of construction (~2027)



CEPC team (domestic)

CEPC accelerator and detector/experiments/theory group is an highly experienced team with strong international collaboration experiences. It has demonstrated its expertise and achievements is the following related projects, both domestic and international ones, such as:

BEPC-BEPCII (BES-BESIII), BFELP, CSNS, ADS, HEPS, LEP, LHC, LHCb, ILC, EXFEL, HL-LHC, BELLE, BELLE-II, CLEO, Daya Bay, JUNO, etc.

CEPC international partners and collaborators



Summary

- The CEPC TDR optimizations designs with high luminosity (30MW and 50MW) operations for all four energies (Higgs, W/Z and ttbar) satisfy the CEPC scientific goals.
- CEPC accelerator TDR international review and cost review were held from June 12-16, 2023 and Sept. 11-15, 2023, respectively, and endorsed by IAC meeting held from Oct. 30-31, 2023. CEPC Accelerator TDR has be released formally on December 25, 2023 and published in Journal Radiation Detection Technology and Methods (RDTM) on June 3, 2024: DOI: 10.1007/s41605-024-00463-y https://doi.org/10.1007/s41605-024-00463-y
- EDR site selection and site dependent engineering design have already been started
- Detailed preparation of CEPC EDR phase (2024-2027) before construction working plan and beyond have been established with the aim for CEPC proposal to be presented to and selected by Chinese government around 2025 for the construction start during the "15th five year plan (2026-2030)" (for example, around 2027) and completion around 2035.
- CEPC Accelerator EDR have progressed well with corresponding EDR budgets and EDR human resources, and will be reviewed by IARC in Sept. 18-20, 2024 at IHEP.
- A beam driven PWFA experimental program has been initialized and started at IHEP to address the cascade and e+ accelerations aiming on future plasma injector for CEPC and future linear colliders.
- International collaboration and participation are warmly welcome.



Thanks for your attention